

	DIRECTORATE GENERAL OF HYDROCARBONS (Ministry of Petroleum & Natural Gas) OIDB Bhawan, Plot No. 2, Sector 73, Noida -201 301. Phone: +91-0120-247- 2000 Email: mm@dghindia.gov.in
---	---

Addendum / Corrigendum No. 1. MM-12019/12/2017-DGH/ENQ-066 for Renovation work in DG Conference Room at 2nd Floor, OIDB Bhawan, Noida.

		In lieu of	Read as
Sl. No.	Tender Clause No.	Details	Details
1	Item at Sr. No. 8e of Table A, For Audio-visual System/ facilities of Annexure-V at Page No. 77	Heavy duty good quality moulded VGA with audio cable-35 feet	Heavy Duty Good quality moulded HDMI cable -35 feet
2	Cl. F.3, Section C, of Annexure-III	Timely intimation to client about lamp usage and any kind of consumable items required for operation of system.	Timely intimation to client about lamp usage and any kind of consumable items including replacement of same for operation of the system.
3	Sr. No. 1.10, Appendix-D1/2, Section D, of Annexure-III	Motorised Screen: Certification: UL,CE, FCC	Deleted
4	Item at Sr. No. 1 of Table B, For Electrical/civil work of Annexure-V Page No. 78	Providing and laying wooden frame inside conference room all walls with 50 mm glass wool filling having density of 24. providing and fixing wooden section vertical and horizontal of 2'x2' size for giving strength to outer ply and making wall structures with 1/2" thick marine grade ply , back side 0.8 mm laminate finish and front side finished 1/2" ply + 4mm ply then 4mm veneer. (Veneer- basic rate Rs. 120/- per sft). (Cost of polish shall not be counted separately it is all inclusive). Make: Board, ply and veneer - Greenlam/Century/Duro)	Providing and laying wooden frame inside conference room all walls with 50 mm glass wool filling having density of 24. providing and fixing wooden section vertical and horizontal of 2'x2' size for giving strength to outer ply and making wall structures with 1/2" thick marine grade ply , back side 0.8 mm laminate finish and front side finished 1/2" ply + 4mm ply then 4mm veneer. (Veneer- basic rate Rs. 120/- per sft). (Inclusive of cost of melamine polish). Make: Board, ply and veneer - Greenlam/Century/Duro)

5	Item at Sr. No. 5 of Table B, For Electrical/civil work of Annexure-V Page No. 78	Providing and fixing of wooden console made of 19mm board, pasting of laminate 0.8 mm inside and veneer 4 mm external with polishing (Cost of paint and polish shall not be counted separately) (Size: 14' X 1.6' X 3') (Make: Board, ply and veneer - Greenlam/Century/Duro) (Make: Hardwares - Hardwyn/Hafele/Hettich/Blum)	Providing and fixing of wooden console made of 19mm board, pasting of laminate 0.8 mm inside and veneer 4 mm external with melamine polishing (inclusive of cost of paint and melamine polish) (Size: 14' X 1.6' X 3') (Make: Board, ply and veneer - Greenlam/Century/Duro) (Make: Hardwares - Hardwyn/Hafele/Hettich/Blum)
6	Cl. No. 15 of Section-D2	NIL	<u>Safety:</u> i) The contractor will be solely responsible for safety of man, machineries and property at the site and should follow all the safety norms and practice. Any safety gadget required for the work is contractor's responsibility. ii) There should not be any disturbance or obstruction of daily operation and work flow of DGH for work to be executed by the contractor under this contract. iii) For entry of the contractor's personnel, labors and materials etc. to the work site, prior permission would be required to be taken by the contractor in advance from the competent authority of DGH.
7	Cl. No. 16 of Section-D2	NIL	Any minor activity/ies not included in the Scope of work/Price format/Price Schedule, but is/are essentially required to complete the work on turnkey basis, will be in the scope of contractor.

Ankit Gupta
EE (M)-MM
For DG, Directorate General of Hydrocarbons