

**DIRECTORATE GENERAL OF HYDROCARBONS**

(Ministry of Petroleum & Natural Gas)

OIDB Bhawan, Plot No. 2, Sector 73, Noida-201301, India.

Phone: 0120-247 2000, Fax- 247 2049. email- mm@dghindia.gov.in

CORRIGENDUM NO. 2

In respect of Open E-Tender No. MM-14/16/2018-DGH/ENQ-142 for “Refurbishment of G & G data interpretation centre”, e-bid closing date is hereby extended from 31th January 2019 to 07th Feb 2019. The revised e-bid closing/opening time & date for the above tender is as under:

E-Bid Closing Date & Time : 07th Feb 2019 at 1400 Hrs (IST)

E-Bid Opening Date & Time : 08th Feb 2019 at 1500 Hrs (IST)

BOQ/Price schedule has been modified/revised as per Annexure enclosed herewith. Addendum/ Corrigendum / Bid Due Date Extensions, if any, to the Bid Document shall be uploaded on DGH’s website www.dghindia.gov.in and Government of India’s Public Procurement Portal <http://eprocure.gov.in/cppp/> only. Hence, bidders shall view the said websites regularly.

HOD (MM)

For Directorate General of Hydrocarbons

Annexure-I

Ref: BOQ/ Price Schedule of E-Tender No. MM-14/16/2018-DGH/ENQ-142 for Refurbishment of G & G data interpretation centre.

The following **line items of BOQ/ Price schedule has been modified/ revised**. Bidder is requested to consider these changes/ modification in their offer while submitting the bid:

Sl. No.	Item Description	Item Description
	Existing	Revised/ Modified
1.04	Providing and fixing 50 mm x 25 mm timber framing for partition wall of hard wood (Kailwood) @ 600mm centre to centre. Necessary provisions for spaces & cut outs for electrical conduits, socket/ switches to be made as per required. The frames are duly treated with anti-termite and fire retardant paint. etc complete.	Providing and fixing 50 mm x 50 mm timber framing for partition wall of hard wood (Kailwood) @ 600mm centre to centre. Necessary provisions for spaces & cut outs for electrical conduits, socket/ switches to be made as per requirement. The complete frames are duly treated with anti-termite and fire retardant paint. etc.
1.06	Providing and fixing of work stations and makes for board, ply, veneer and hardwares are used as directed by EIC. Necessary provisions for spaces & cut outs for electrical conduits, socket/ switches to be made as per required .	Providing and placing workstation with partition thickness of 35mm thk. Duro commercial plywood or equivalent, and 1200mm Ht. with matching 1 mm laminate (Greenlam or equivalent) with PVC lapping. Workstation of size 1800mm w x 900mm d x 750mm Ht. each - 25mm thk commercial plywood (Duro or equivalent) matching with 1 mm thk. laminate (Greenlam or equivalent) with lapping edge beading free standing office desk with pedestal of size 450mm w x 600mm d x 700mm ht. with 3 drawers (2 box + 1 file), CPU trolley with keyboard tray pencil type with/without mouse tray - plastic /metal. Necessary hardwares, provisions for spaces & cut outs for electrical conduits, socket/ switches to be made as per required etc. complete as directed by EIC. Note :- All partition have proper levelled and fixed with the existing floor.

Note: Respective Qty. of aforesaid line items will remain same as defined in original BOQ/ Price Schedule.